GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

EFS&T Department – Digging of Peripheral Trenches / Water Absorption Trenches (WAT) / Elephant Proof Trenches (EPT) on the boundaries of Forest Blocks in the state for boundary protection and water conservation - Finalization of rates and specifications – Approval accorded - Orders – Issued.

ENVIRONMENT, FORESTS, SCIENCE AND TECHNOLOGY (Sec.II) DEPARTMENT

G.O.MS.No. 61 **Dated.06.07.2015**

Read:-

From PCCF& HoFF, A.P, Hyderabad Lr No. 6574/2015/Sch.III/AP, Dt.20.06.2015.

*****

ORDER:-

In the circumstances reported by the Principal Chief Conservator of Forests & Head of Forest Force, Andhra Pradesh, Hyderabad in the reference read above, Government after careful examination of the proposal, hereby approve the rate of Rs. 40.10 per Cmt for excavation of peripheral trenches/water absorption trenches/elephant proof trenches without trimming, involving earth work excavation by the excavator with shovel 0.5 cum capacity in all kinds of soil including boulders upto 0.3 Mt diameter, leaving the berm of 1.5 Mt from the edge of the trench in rough trapezoidal shape.

2. The top width, bottom width and depth of the trench shall generally be 3 Mts, 2 Mts and 3 Mts. respectively. The bottom width may be suitably modified between 1.5 Mt to 2 Mt for ensuring stability of side slopes in different soil types in accordance with IS Code 4701:1982, Pg.7.

3. This order issues with the concurrence of Finance (EBS VII, MA &F) Department vide their U.O No. 055/A2/EBS -VII/2015, Dated. 06.07.2015.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

ASHWINI KUMAR PARIDA
SPECIAL CHIEF SECRETARY TO GOVERNMENT

To
The Principal Chief Conservator of Forests & Head of Forest Force,
Andhra Pradesh, Hyderabad.

Copy to:
The Water Resources (Reforms) Department.
The Finance (EBS VII, MA &F) Department.
SF/ SC

//FORWARDED::BY ORDER//

SECTION OFFICER